START OF APPROVAL OF PLAN

SHEET NO 1 / 5

SUMMARY & BALCONY AREA STATEMENT WING A + B							STAIRCASE AREA IN PREMIUM		
FLOOR	B/UP AREA IN SQMT			PERM AREA (10% OF B UP)	PROP AREA	EXCESS AREA			
	WING A	WING B	TOTAL				WING A	WING B	TOTAL
GROUND	--	--	--	--	--	--	--	--	--
FIRST	253.76	299.74	553.50	55.35	52.14	NIL			
SECOND	253.76	--	253.76	25.37	25.12	NIL			
THIRD	253.76	--	253.76	25.37	25.12	NIL			
FOURTH	253.76	--	253.76	25.37	25.12	NIL			
FIFTH	235.59	--	235.59	23.55	22.98	NIL			
SIXTH	253.76	--	253.76	25.37	25.12	NIL			
SEVENTH	253.76	--	253.76	25.37	25.12	NIL			
EIGHTH	235.59	--	235.59	23.55	22.98	NIL			
NINETH	253.76	--	253.76	25.37	25.12	NIL			
TENTH	253.76	--	253.76	25.37	25.12	NIL			
ELEVENTH	235.59	--	235.59	23.55	22.98	NIL			
TWELTH	253.76	--	253.76	25.37	25.12	NIL			
THIRTEEN	253.76	--	253.76	25.37	25.12	NIL			
FOURTEEN	235.59	--	235.59	23.55	22.98	NIL			
FIFTEEN	187.95	--	187.95	18.79	17.12	NIL			
TOTAL	3667.91	299.74	3987.65	398.49	395.26	NIL			

SCHEDULE OF DOORS & WINDOWS			
TYPE	SIZE	AREA	REMARKS
RS	2.10 X 2.40	5.04	ROLLING SHUTTER
D	0.99 X 2.13	2.11	T.W. PANNELLED DOOR
D1	0.91 X 2.13	1.94	T.W. PANNELLED DOOR
D2	0.76 X 1.98	1.50	T.W. PANNELLED DOOR
W	1.80 X 1.20	2.16	T.W. GLAZED WINDOW
W1	1.50 X 1.20	1.80	T.W. GLAZED WINDOW
W2	1.20 X 1.00	1.20	T.W. GLAZED WINDOW
V	0.61 X 0.90	0.55	T.W. LOUVERS WINDOW



LOCATION PLAN
(SCALE 1:2500)



BLOCK PLAN
SCALE 1:500

N



GROUND FLOOR PLAN
-BLDG.NO.1
SCALE 1: 100



B/UP AREA STATEMENT (RESERVATION) SANCTION NO.318					
RESERVATION NO	100 % OF AREA	40 % OF 100% PLOT AREA	40 % OF 100% PLOT AREA 40 % B/UP AREA	PROPOSED AREA	TOTAL
M.S.E.D.C.L. - 318	3340.00 SQMT	1336.00 SQMT	534.40 SQMT	GRD + 1ST 267.92+267.92	535.84 SQMT



PLOT AREA CALCULATION
SCALE 1:500

SET BACK AREA				
1	1/2 X 26.00 X 8.48 X 1NO	=	102.96 SQ.MT.	
2	1/2 X 26.00 X 10.078 X 1NO	=	131.02 SQ.MT.	
	TOTAL ADDITION	=	241.00 SQ.MT.	
1	1/2 X 21.35 X 11.06 X 1NO	=	118.07 SQ.MT.	
2	1/2 X 24.69 X 5.38 X 1NO	=	66.54 SQ.MT.	
3	1/2 X 24.69 X 1.01 X 1NO	=	12.47 SQ.MT.	
4	1/2 X 40.32 X 7.95 X 1NO	=	160.47 SQ.MT.	
5	1/2 X 19.02 X 3.98 X 1NO	=	37.85 SQ.MT.	
6	1/2 X 12.94 X 3.33 X 1NO	=	21.60 SQ.MT.	
	TOTAL ADDITION	=	417.00 SQ.MT.	
c	1/2 X 24.52 X 0.40 X 1NO	=	4.90 SQ.MT.	
b	1/2 X 24.52 X 0.99 X 1NO	=	12.14 SQ.MT.	
c	1/2 X 14.98 X 5.21 X 1NO	=	37.98 SQ.MT.	
d	1/2 X 36.86 X 6.72 X 1NO	=	124.25 SQ.MT.	
e	1/2 X 32.21 X 1.35 X 1NO	=	21.74 SQ.MT.	
f	1/2 X 23.44 X 1.52 X 1NO	=	17.81 SQ.MT.	
g	1/2 X 13.22 X 2.45 X 1NO	=	16.19 SQ.MT.	
	TOTAL ADDITION	=	235.00 SQ.MT.	
1	1/2 X 44.33 X 20.82 X 1NO	=	461.46 SQ.MT.	
2	1/2 X 44.33 X 3.77 X 1NO	=	83.56 SQ.MT.	
3	1/2 X 50.58 X 12.05 X 1NO	=	304.99 SQ.MT.	
4	1/2 X 50.58 X 8.72 X 1NO	=	220.55 SQ.MT.	
5	1/2 X 51.87 X 10.04 X 1NO	=	260.39 SQ.MT.	
7	1/2 X 43.39 X 8.68 X 1NO	=	188.31 SQ.MT.	
8	1/2 X 43.31 X 13.23 X 1NO	=	286.50 SQ.MT.	
9	1/2 X 49.66 X 11.85 X 1NO	=	269.44 SQ.MT.	
10	1/2 X 50.10 X 4.786 X 1NO	=	119.39 SQ.MT.	
11	1/2 X 50.10 X 12.57 X 1NO	=	314.85 SQ.MT.	
12	1/2 X 35.56 X 2.00 X 1NO	=	35.58 SQ.MT.	
13	1/2 X 35.56 X 13.86 X 1NO	=	246.43 SQ.MT.	
14	1/2 X 22.79 X 5.63 X 1NO	=	64.15 SQ.MT.	
15	1/2 X 10.05 X 2.66 X 1NO	=	13.37 SQ.MT.	
	TOTAL ADDITION	=	2930.00 SQ.MT.	
a	1/2 X 6.90 X 4.01 X 1NO	=	13.83 SQ.MT.	
b	1/2 X 6.90 X 1.55 X 1NO	=	5.35 SQ.MT.	
c	1/2 X 17.58 X 2.485 X 1NO	=	21.85 SQ.MT.	
d	1/2 X 21.83 X 0.88 X 1NO	=	9.61 SQ.MT.	
e	1/2 X 27.64 X 0.84 X 1NO	=	11.61 SQ.MT.	
f	1/2 X 37.36 X 11.14 X 1NO	=	208.10 SQ.MT.	
g	1/2 X 37.39 X 22.06 X 1NO	=	412.08 SQ.MT.	
h	1/2 X 35.02 X 5.12 X 1NO	=	89.65 SQ.MT.	
i	1/2 X 7.12 X 3.63 X 1NO	=	12.92 SQ.MT.	
	TOTAL ADDITION	=	785.00 SQ.MT.	
TOTAL ADDITION=241+417+235+2930+785.00		=	4610.00 SQ.MT.	
NET PLOT AREA		=	4610.00 SQ.MT.	



GROUND FLOOR PLAN
SCALE 1:200

STILT FLOOR PLAN
BLDG. NO.1
SCALE 1:200

LAYOUT PLAN
SCALE 1:200

N

LIGHT AND VENTILATION STATEMENT					
ROOM NAME	AREA (SQMT)	L/V REQUIRED	PROVIDED	SQMT	TYPE	SIZE
LIVING	9.50	1.58	4.32		FW1	1.80 X 2.40
BEDROOM	7.52	1.25	4.32		FW1	1.80 X 2.40
STUDY ROOM	5.50	0.92	4.32		FW1	1.80 X 2.40
KITCHEN	5.50	0.92	1.44		W2	1.80 X 1.20
DINING	5.50	0.92	1.44		W2	1.20 X 1.20
BATH	1.80	0.30	0.54		V	0.60 X 0.90
W.C.	1.08	0.30	0.54		V	0.60 X 0.90
TOILET	2.52	0.30	0.54		V	0.60 X 0.90

AREA STATEMENT

			SQ.MT.
1	AREA OF PLOT AS PER 7/12	(S.NO.131 (49) H.NO.5/1 = 660.00 (S.NO.131 (49) H.NO.6 = 1020.00 (S.NO.131 (49) H.NO.7 = 1060.00 (S.NO.131 (48) S.NO.8 = 760.00 (S.NO. 31 (43) H.NO. 13 = 970.00	4610.00
	AREA OF PLOT AS PER TRINGULATION METHOD		4610.00
2	DEDUCTION FOR		
	a EXISTING ROAD		
	b PROPOSED ROAD(SET-BACK AREA) 45.00 M.D.P.ROAD = 241.00 sq.mt.		241.00
	c ANY RESERVATION NALLA AREA		201.00
	d NOT IN POSSESION		16.00
	e TOTAL AREA (a+b+c+d) (241.00 + 201.00 + 16.00)		458.00
3	BALANCE AREA OF PLOT (4610.00 - 458.00)		4152.00
4	DEDUCTION FOR RECREATION GROUND (4152.00 X 15%)		622.00
	INTERNAL ROAD		
5	NET AREA OF PLOT (3-4) (4152.00 - 622.80)		3529.20
6	ADDITION FOR F.S.I. (2a) 241.00 x 2.10 = 506.10		506.10
7	TOTAL AREA (3529.20 + 506.10)		4035.30
8	F.S.I. PERMISSIBLE		ONE
9	F.S.I. CREDIT AVAILABLE T.D.R. (4152.00 X 1.40 % = 5812.80) (5812.80 - 506.10 = 5306.70)		
10	PERMISSIBLE FLOOR AREA		4035.30
11	EXISTING FLOOR AREA		
12	PROPOSED FLOOR AREA		3987.65
13	EXCESS BALCONY AREA		
14	TOTAL PROPOSED BUILT- UP AREA (11+12+13)		3987.65
15	F.S.I. CONSUMED		0.98

BALCONY AREA STATEMENT

a	PERMISSIBLE BALCONY AREA	AS SHOWN
b	PROPOSED BALCONY AREA	
c	EXCESS BALCONY AREA	

TENEMENT STATEMENT

a	PROPOSED AREA	3987.65
b	LESS DEDUCTION OF NON -RESIDENTIAL AREA	NIL
c	AREA OF TENEMENT (a+b)	3987.65
e	TENEMENT PERMISSIBLE	119
f	TENEMENT PROPOSED	75
g	TENEMENT EXISTING	
h	TOTAL NO.OF TENEMENT	75

PARKING STATEMENT

a	PARKING REQUIRED BY RULE, CAR	AS SHOWN
	SCOOTER	
	CYCLE	

APPENDIX - C

THE PLANS PREPARED BY ME ARE IN ACCORDANCE WITH THE NORMS AS SPECIFIED BY INDIAN STANDARD INSTITUTE & I WILL BE HELD RESPONSIBLE FOR ANY HARM CAUSED IN EARTHQUAKE DUE TO NEGLIENCE OF THE STANDARDS.

SHANTI CONSULTANTS
M.C.C Structural Engineers-Arvind S. Patel
Reg. No. STR/781, ASAE Reg. No. 478

ENGINEERS SIGNATURE

CERTIFICATE OF AREA

CERTIFIED THAT THE UNDER REFERENCE WAS SURVEYED BY ME ON 10-07-18 & THE THE DIMENSIONS OF SIDES ETC. OF PLOT STATED ON PLAN ARE AS MEASURED ON SITE AND AREA SO WORKED OUT IS 4610.00 SQ.MT. & TALLIES WITH THE AREA STATED IN DOCUMENTS OF OWNERSHIP T.P. SCHEME RECORD/ CITY SURVEY RECORD/LAND RECORD DEPARTMENT

SIGN OF ARCHITECT

DESCRIPTION OF PROPOSAL & PROPERTY

PROPOSED RESIDENTIAL BUILDING ON PLOT BEARING
S. NO. 131 (OLD) , S.NO. 49 (NEW) , H. NO. 5/1,6,7, 8,13
AT VILLAGE GAONDEVI, DOMBIVLI (W), TAL. KALYAN, DIST. THANE
FOR SHRI:- VIJAY BABU MHATRE
FOR SHRI:- DILIP K MORE (P.A. HOLDER)
M/S. ONKARESHWAR DEVELOPERS
ONKARESHWAR DEVELOPERS
SHRI :- SANJAY. R. SINGH (PARTNER)
PARTNER

ARCHITECT	CONSULTING ARCHITECT
DE-CON ASSOCIATES ARCHITECTS & INT. DESIGNERS S-1 / RAJSHREE TOWER RAM BAUG, LANE No 5 KALYAN (W) CA. No. 92/15118	TIBIN TONSON THOMAS ARCHITECTS & INT. DESIGNERS B-2 / ROOM NO.233 / KASTURI PLAZA, DOM (E) CA. No. 2016 / 76885