SHEET NO. 35

TYPE-Q1

SECTOR NO V, VI, VII



ELEVATION

VIEW A-A



SECTION B-B

SCALE 1:100



AREA DIAGRAM (GR & TYP FLOOR)

SCALE 1:200

BUILT UP AREA CALCULATION OF GR & TYP. FLOOR

RECTANGLE AREA=13.45X10.75=144.58 SQMTS

DEDUCTION

1	2.45	X 0.90 X	1	=	SQMT
2	2.75	X 1.80 X	2	=	SQMT
3	3.05	X 0.90 X	1	=	SQMT
4	0.90	X 3.15 X	2	=	SQMT
5	2.45	X 5.15 X	1	=	12.62 SQMT
6	8.55	X 0.90 X	1	=	SQMT
		TOTAL		=	41.15 SQMT

BUILT-UP AREA FOR PER FLOOR

(144.58 - 41.15) = 103.43 SQMT

BALCONY AREA CALCULATION FOR TYPICAL FLOOR

B1	2.45 X 0.90 X 3	=	6.61	SQMT
B2	2.75 X 0.90 X 2	=	4.95	SQMT
B3	3.05 X 0.90 X 2	=	5.49	SQMT
	TOTAL	=	17.05	SQMT
PERMISSIBLE BAL AREA		=	10.34	SQMT
PROPOSED BAL AREA		=	17.05	SQMT
EXCESS BAL AREA		=	6.71	SQMT

PARKING AREA STATEMENT

TENEMENT	NO OF FLATS	REQUIRED	PROVIDED
<35 SQMTS	20 FLATS	--	--
35 TO 45 SQMT	--	--	--
TOTAL	20 FLATS	--	--

TOTAL BUILT UP AREA STATEMENT

FLOOR	BUILT UP AREA	EXCESS BALCONY	TOTAL B/U AREA
GR. FLOOR	103.43 SQMT	6.71 SQMT	110.14 SQMT
1ST FLOOR	103.43 SQMT	6.71 SQMT	110.14 SQMT
2ND FLOOR	103.43 SQMT	6.71 SQMT	110.14 SQMT
3RD FLOOR	103.43 SQMT	6.71 SQMT	110.14 SQMT
4TH FLOOR	103.43 SQMT	6.71 SQMT	110.14 SQMT
TOTAL	517.15 SQMT	33.59 SQMT	550.70 SQMT

TOTAL CONSTRUCTION AREA STATEMENT

FLOOR	TOTAL B/U AREA	BALCONY AREA	STAIR CASE AREA	TOTAL CON.AREA
GR. FLOOR	110.14 SQMT	10.34 SQMT	15.06 SQMT	135.54 SQMT
1ST FLOOR	110.14 SQMT	10.34 SQMT	15.06 SQMT	135.54 SQMT
2ND FLOOR	110.14 SQMT	10.34 SQMT	15.06 SQMT	135.54 SQMT
3RD FLOOR	110.14 SQMT	10.34 SQMT	15.06 SQMT	135.54 SQMT
4TH FLOOR	110.14 SQMT	10.34 SQMT	15.06 SQMT	135.54 SQMT
TOTAL	550.70 SQMT	51.70 SQMT	75.30 SQMT	677.70 SQMT

SCHEDULE OF LIGHT&VENTILATION

ROOM	CARPET AREA	REQUIRED	PROVIDED
LIV	2.75 X 3.80 =10.45	1.74	1.50 X 1.20=1.80
STUDY	2.75 X 3.50 = 9.62	1.60	1.50 X 1.20=1.80
KIT	2.15 X 2.60 = 5.59	0.93	1.20 X 1.20=1.44
ALCOVE	2.15 X 1.70 = 3.65	0.61	1.20 X 1.20=1.44
BATH	1.99 X 1.20 = 2.38	0.40	0.60 X 0.90=0.54
WC	1.20 X 0.91 = 1.09	0.18	0.60 X 0.90=0.54

SCHEDULE OF DOORS&WINDOWS

TYPE	SIZE	DESCRIPTION
D	1.00 X 2.10	T.W FLUSH DOOR
D1	0.90 X 2.10	T.W FLUSH DOOR
D2	0.75 X 2.00	T.W PANNEL DOOR
W1	1.50 X 1.20	ALUMINUM SLIDING WINDOW
W2	1.20 X 1.20	ALUMINUM SLIDING WINDOW
V	0.60 X 0.90	CONCRETE VENTILATOR



GROUND FLOOR PLAN (TYPE-Q1)

SCALE 1:100

VIEW A-A



TYPICAL FLOOR PLAN (1ST TO 4TH)

SCALE 1:100

VIEW A-A



TERRACE FLOOR PLAN

SCALE 1:100

PROFORMA II

CONTENTS OF SHEET

GROUND FLOOR PLAN WITH PLOT LAY OUT,1ST,2ND & TERRACE FLOOR PLAN,BUILT UP AREA STATEMENT,PARKING STATMENT, BALCONY AREA STATEMENT, SECTION,ELEVATION,LOCATION PLAN AND ARCHITECTURAL DRAWINGS.

STAMP OF DATE OF RECEIPT OF PLANS

THIS PLAN SHALL NOT BE CONSIDERED AS A PROOF OF OWNERSHIP, FOR ANY DISPUTES IN ANY COURT OF LAW.

STAMP OF APPROVAL OF PLANS

Subject to ... amended in ... Conditions mentioned in this Office letter. No. CIDCO/VVSR/AM/BP-356/E/1217 Dated. 04/09/2003

ASSOCIATE PLANNER (VVSR)
CIDCO LIMITED,
AMBIKA COMMERCIAL COMPLEX,
SECOND FLOOR, VASAI (EAST),
DIST. THANE.

REVISIONS	DESCRIPTION	DATE	SIGNATURE

CERTIFICATE OF AREA

CERTIFIED THAT THE PLOT UNDER REFERENCE ... SURVEYED BY ME ON 4/7/2002 ... THE DIMENSIONS OF THE SIDE ETC OF THE PLOT STATED ON THE PLANS ... THE AREA SO WORKED OUT TALLIES WITH THE AREA STATED IN THE DOCUMENTS OF OWNERSHIP ... RECORDS DEPT. OF CIDCO'S RECORD

Signature of Licensed Surveyor/Engineer / Structural Engineer / Supervisor

TRUE COPY

ASSOCIATE PLANNER (VVSR) CIDCO LIMITED, AMBIKA COMMERCIAL COMPLEX, SECOND FLOOR, VASAI (EAST), DIST. THANE.

CERTIFIED THAT THE BUILDING PLANS ... SATISFY THE SAFETY REQUIREMENTS FOR STRUCTURES BEING CONSTRUCTED IN SEISMIC ZONE-III IS CORRECT ... TO THE BEST OF MY KNOWLEDGE AND UNDERSTANDING.

IT IS ALSO CERTIFIED THAT THE STRUCTURAL DESIGN ... AGAINST NATURAL HAZARDS HAS BEEN PREPARED BY ... DULY QUALIFIED STRUCTURAL ENGINEER.

SIGNATURE OF LICENSED SURVEYOR

DESCRIPTION OF PROPOSAL & PROPERTY

PROPOSED RESI.& COMM.PROJECT ON PLOT BEARING S.NO.245 H.NO.1 to 4,5, S.NO.246 H.NO.1 PART, S.NO.247 H.NO.1A,1B,1C, S.NO.248 H.NO.1 PART, S.NO.249 H.NO.1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, S.NO.250 H.NO.1, 2, 3, 4, 5, S.NO.251 H.NO.1 PART, S.NO.252 H.NO.1 PART, S.NO.253 H.NO.1 PART, S.NO.254 H.NO.1, 2, 3, 4, S.NO.255 H.NO.1, 2, 3, 4, S.NO.256 H.NO.1, 2, 3, 4, S.NO.257 H.NO.1, 2, 3, 4, S.NO.258 H.NO.1, 2, 3, 4, S.NO.259 H.NO.1, 2, 3, 4, S.NO.260 H.NO.1, 2, 3, 4, S.NO.261 H.NO.1, 2, 3, 4, S.NO.262 H.NO.1 PART, S.NO.263 H.NO.1 PART, S.NO.264 H.NO.1, 2, 3, 4, S.NO.265 H.NO.1, 2, 3, 4, S.NO.266 H.NO.1, 2, 3, 4, S.NO.267 H.NO.1, 2, 3, 4, S.NO.268 H.NO.1, 2, 3, 4, S.NO.269 H.NO.1, 2, 3, 4, S.NO.270 H.NO.1, 2, 3, 4, S.NO.271 H.NO.1, 2, 3, 4, S.NO.272 H.NO.1, 2, 3, 4, S.NO.273 H.NO.1, 2, 3, 4, S.NO.274 H.NO.1, 2, 3, 4, S.NO.275 H.NO.1, 2, 3, 4, S.NO.276 H.NO.1, 2, 3, 4, 5, S.NO.277 H.NO.1, 2, 3, 4, 5, 6, S.NO.278 H.NO.1, 2, 3, 4, 5, 6, 7, 8, S.NO.279 H.NO.1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41,