
BUILT UP AREA (1ST TO 5TH FLOOR) - (RESIDENTIAL)
BLOCK AREA - 19.81 X 39.62 = 784.87 SMT
DEDUCTION -
01) 3.20 x 3.75 x 2 = 23.87
02) 0.84 x 2.51 x 4 = 8.43
03) 3.81 x 2.51 x 2 = 19.12
04) 1.68 x 3.73 x 2 = 11.95
05) 1.68 x 1.60 x 2 = 5.37
06) 2.51 x 2.44 x 2 = 12.24
07) 3.81 x 2.51 x 2 = 19.12
08) 2.51 x 1.37 x 2 = 6.87
09) 2.51 x 2.21 x 1 = 5.54
10) 2.51 x 3.35 x 1 = 8.40
11) 3.20 x 4.65 x 2 = 29.76
12) 1.22 x 4.04 x 2 = 9.85
13) 2.67 x 1.52 x 2 = 8.11
14) 1.75 x 4.04 x 2 = 14.14
15) 3.35 x 1.30 x 2 = 8.71
16) 1.14 x 0.69 x 2 = 1.57
17) 5.11 x 2.82 x 2 = 28.82
18) 7.47 x 3.81 x 1 = 28.46
D1) 3.96 x 1.68 x 2 = 13.30
D2) 1.98 x 1.68 x 2 = 6.65
D3) 1.75 x 2.59 x 2 = 9.06
D4) 1.75 x 1.98 x 1 = 6.93
D5) 1.30 x 1.75 x 2 = 4.55
TOTAL = 290.80
STAIRCASE , PASS. AND LIFT -
P1) 4.88 x 1.68 x 2 = 16.39
P2) 1.68 x 27.74 x 1 = 46.60
L1) 2.21 x 2.29 x 2 = 10.12
S1) 3.35 x 5.49 x 1 = 18.39
TOTAL = 91.50
FIRE STAIRCASE
F1) 3.35 x 5.49 x 1 = 18.39
TOTAL = 18.39
TOTAL DEDUCTION - (290.80+91.50+18.39) = 400.69 SMT
FLOOR BUILT UP AREA - (784.87 - 400.69) = 384.18 SMT
FIRST FLOOR AREA LINE DIAGRAM
SCALE - 1:100
Parking Area Satements
SR. NO. | PARKING SPACE FOR EVERY FLAT OF CARPET AREA | FOUR WHEELERS No.of parking | REQ. | PROP. | TWO WHEELERS No.of Flats | REQ. | PROP.
1) CARPET AREA UP TO 35.0 Sq.mtr. | 1 for 4 flat | 784.87 / 4 = 19.75 | 19.00 | 4/4 | 784.87 / 4 = 75.00 | 75.00
2) CARPET AREA (35.00 SMT TO 45.00 SMT) | 1 for 2 flat | 0.00 | 0.00 | 2/2 | 0.00 | 0.00
3) CARPET AREA (45.00 SMT TO 60.00 SMT) | 1 for 1 flat | 0.00 | 0.00 | 2/1 | 0.00 | 0.00
4) CARPET AREA EXCEEDING 60.00 SMT EACH | 2 for 1 flat | 0.00 | 0.00 | 2/1 | 0.00 | 0.00
Visitor parking (10%) | — | — | 2.00 | — | — | 8.00
Total - 21.00 Total - 83.00
Net parking required (4-WHEELER) - 21 No.
Net parking proposed (4-WHEELER) - 21 No.
Net parking required (2-WHEELER) - 83 No.
Net parking proposed (2-WHEELER) - 83 No.
LOCATION PLAN
SCALE 1:5000
SITE UNDER REFRENCE S. no. 205 (OLD S. NO. 52, H. NO. 3 & 4)
AREA LINE DIAGRAM (R.G.)
SCALE - 1 : 500
R.G. Area Calculation - (TRIANGULATION)
1) = ½ x 19.00 X 7.50 = 71.25 SMT.
2) = ½ x 27.25 X 11.25 = 153.28 SMT.
3) = ½ x 43.25 X 5.00 = 108.12 SMT.
TOTAL AREA = 332.65 SMT.
STAIRCASE , PASS. AND LIFT - AREA CALCULATION GROUND FLOOR -
P1) 3.35 x 5.33 x 1 = 17.85
P2) 3.43 x 2.29 x 2 = 15.70
TOTAL = 33.55
STAIRCASE , PASS. AND LIFT - AREA CALCULATION FIRST FLOOR -
P1) 4.88 x 1.68 x 2 = 16.39
P2) 1.68 x 27.74 x 1 = 46.60
L1) 2.21 x 2.29 x 2 = 10.12
S1) 3.35 x 5.49 x 1 = 18.39
TOTAL FLOOR ST./ PASS/LIFT AREA = 91.50
FIRE STAIRCASE
F1) 3.35 x 3.49 x 1 = 18.39
TOTAL = 18.39
CUB AREA STATEMENT
C1) 2.29 x 0.46 x16 = 12.36
TOTAL = 12.36
TOTAL PROPOSED AREA OF STAIRCASE,PASSAGE, LIFT, BALCONY AND CUB. (FIRST FLOOR)
(91.50 + 12.36) = 103.86
TOTAL = 103.86
LAYOUT OF RAIN WATER HARVESTING TANK
BORE WELL
SECTION ALONG A-A"
(SCALE - 1 : 50)
Sieves (6 th)
15%-Open(2'-0" depth)
Coarse Sand(2'-0"depth)
Permeable Net
Wood charcoal (2'-0"depth)
Permeable Net
20mm-Gravel(2'-0" depth)
Permeable Net
40mm-Gravel(2'-0"depth)
0.15 p.c.c
0.23 soiling
TOTAL PROPOSED BUILT UP AREA
FLOOR LEVEL | COMMERCIAL | RESIDENTIAL
GROUND FL. | ——— | ———
FIRST FLOOR | ——— | 384.18 Sq.mtr.
SECOND FLOOR | ——— | 384.18 Sq.mtr.
THIRD FLOOR | ——— | 384.18 Sq.mtr.
FOURTH FLOOR | ——— | 384.18 Sq.mtr.
FIFTH FLOOR | ——— | 384.18 Sq.mtr.
TOTAL AREA | ——— | 1920.90 Sq.mtr.
TOTAL B/U AREA - 1920.90 SMT
SCHEDULE OF DOORS AND WINDOWS
SYMBOL | SIZE | REMARKS
D1 | 1.07x2.13 | DOOR
D2 | 0.91x2.13 |
D3 | 0.76x1.83 |
W1 | 2.13x1.83 | WINDOW
W2 | 1.83x1.83 |
W3 | 0.61x0.76 |
V | 0.61x0.76 | VENTILATOR
ITEM | PERMISSIBLE | PROPOSED | | EXCESS AREA
STAIRCASE , LIFT, PASS AND CUB | 1990.44 X 30% = 597.13 | 1 ST./PASS/LIFT (G.F.) = 33.55
1 ST./PASS/LIFT (1ST) - CUB (1ST) = 86.85
TOTAL = 103.86 - 3.5 FIL. = 100.36
(33.55 + 100.36) = 133.91 | 26.14 sq.mtr.
WATCHMAN CABIN | | 3 | 4.39 |
SOCIETY OFFICE | | 4 | 17.10 |
METRE ROOM | | 5 | 12.15 |
GYM WATER TANK | | 6 | 26.78 |
TOTAL AREA (1+2+3+4+5+6) | | | 623.27
PLOT AREA LINE DIAGRAM AND CALCULATION
PLOT AREA LINE DIAGRAM
AREA GOING UNDER 15 M WIDE ROAD
TOTAL
Plot Area Calculation - (TRIANGULATION)
1) = ½ x 50.00 (12.50+16.00) = 712.50 SMT.
2) = ½ x 47.00 x 9.50 = 223.25 SMT.
3) = ½ x 54.00 x 20.00 = 540.00 SMT.
4) = ½ x 55.00 x 6.00 = 165.00 SMT.
5) = ½ x 55.00 x 30.50 = 838.75 SMT.
TOTAL AREA = 2479.50 SMT.
AREA GOING UNDER 15.00 M W ROAD
a) = ½ x 10.50 x 2.00 = 10.50 SMT.
b) = ½ x 57.75 x 6.50 = 187.68 SMT.
c) = ½ x 51.00 x 5.75 = 146.62 SMT.
TOTAL AREA = 344.80 SMT.
SOCIETY OFFICE
A
B
AREA LINE DIAGRAM OF SOCIETY OFFICE
METRE ROOM
AREA LINE DIAGRAM OF METRE ROOM
SEPTIC TANK PLAN (SCALE - 1:50)
SECTION OF SEPTIC TANK (SCALE - 1:50)
PERCULATION PIT
SCALE - 1:100
SCHEDULE OF DOORS AND WINDOWS
SYMBOL | SIZE | REMARKS
D1 | 1.00x2.10 | DOOR
D2 | 0.90x2.10 |
D3 | 0.75x1.80 |
W1 | 2.10x1.80 | WINDOW
W2 | 1.80x1.80 |
W3 | 0.60x0.75 |
W4 | 1.20x1.80 |
V | 0.60x0.75 | VENTILATOR
SECTION OF COMPOUND WALL
SCALE - 1:50
CARPET AREA OF EACH FLAT (ST. + 5 FL.)
TYPE | CARPET AREA | NO. OF FLATS | FLAT NO.
1 BHK | 32.20 SQ.M. | 10 | 101 AND 113 , 201 AND 213, 301 AND 313 401 AND 413 , 501 AND 513.
1 BHK | 31.26 SQ.M. | 10 | 102 AND 112 , 202 AND 212, 302 AND 312 402 AND 412 , 502 AND 512.
1 RK | 18.39 SQ.M. | 10 | 103 AND 111 , 203 AND 211, 303 AND 311 403 AND 411 , 503 AND 511.
1 RK | 18.45 SQ.M. | 10 | 104 AND 110 , 204 AND 210, 304 AND 310 404 AND 410 , 504 AND 510.
1 RK | 18.24 SQ.M. | 35 | 105 , 106 , 107 , 108 , 109 , 114 AND 115 , 205 , 206 , 207 , 208 , 209 , 214 AND 215 , 305 , 306 , 307 , 308 , 309 , 314 AND 315 , 405 , 406 , 407 , 408 , 409 , 414 AND 415 , 505 , 506 , 507 , 508 , 509 , 514 AND 515 .
TOTAL NUMBER OF FLATS - 75
SITE PLAN
SCALE - 1:500
UNDER GR. WATER TANK 149.3 SQ.M.
SCOUTING PARKING 66.72 SQ.M.
WATCHMAN CABIN 2.44 SQ.M.
ADJ. S.NO.53
ADJ. S.NO.52
ADJ. S.NO.51
ADJ. S.NO.54
ADJ. S.NO.55
ADJ. S.NO.56
ADJ. S.NO.57
ADJ. S.NO.58
ADJ. S.NO.59
ADJ. S.NO.60
ADJ. S.NO.61
ADJ. S.NO.62
ADJ. S.NO.63
ADJ. S.NO.64
ADJ. S.NO.65
ADJ. S.NO.66
ADJ. S.NO.67
ADJ. S.NO.68
ADJ. S.NO.69
ADJ. S.NO.70
ADJ. S.NO.71
ADJ. S.NO.72
ADJ. S.NO.73
ADJ.

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT











STAMP FOR APPROVAL
SHEET NO. 02 OF 02 | 02

PLANS APPROVED (...02...) NOS OF DRAWINGS) WHICH ARE TO BE READ ALONG WITH COMMENCEMENT CERTIFICATE / AMENDED COMMENCEMENT CERTIFICATE ISSUED UPTO PLINTH LEVEL BEARING NO. [illegible] DATED [illegible] AND THE CONDITIONS MENTIONED THEREIN

Planner,
Planning Division
KMPDA

PROPERTY DISCRIPTION

THE PLAN OF PROPOSED RESEIDENTIAL BUILDING ON LAND BEARING S.NO. 205 H.NO. 3 & 4 (OLD S.NO.52, H.NO. 3 & 4) AT VILLAGE - ANJUR , TALUKA- BHIWANDI , DIST.-THANE

OWNERS SIGNATURE

ENGINEER'S NAME AND SIGNATURE

Fouzi & Associates
ENGINEERS & R.C.C. CONSULTANT
Fouzi & Associates
ARCHITECT & RCC CONSULTANTS PUNE
72/73, 2nd Nizampura,
Bhiwandi - 421 302. Dist. Thane

DRAWN BY	CKD	SCALE	DATE	JOB NO.	DRG.NO.
SIRAJ T KHAN	A.MOMIN	1:50, 1:100	20.11.2017		

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT