

मुख्य कार्यालय, विरार
विरार (पूर्व),
सा. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५२०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५२०७
ई-मेल : vasavirarcorporation@yahoo.com

जावक कः व.वि.श.म.
दिनांक :

Dated ५/08/2015

VVCMC/TP/CC/NP-5731/2406/2015-16

To,
Damjji bhanushali,
Kishore kunj,
Behind Vartak Engineering college,
Navghar Vasai (W)
Tal :- Vasai, Dist :- Palghar.

SUB -- Commencement Certificate for proposed Residential Building on land bearing S.No.21 Plot No.43 of Village: Navghar, Taluka: Vasai, Dist: Palghar.

Ref -- 1) Your Architect's letter dated 07/07/2015.

Sir / Madam,

Find enclosed Assessment order issued herewith as per Sec 124 E of MRTP Act 1966.

1	Name of Assessee owner / P.A. Holder	:	Damjji bhanushali,	Navghar				
2	Location	:		Residential				
3	Land use (Predominant)	:						
4	Gross Plot Area	:	484.08	Sqm.				
5	Deduction : Additional Road Widening	:	0.00	Sqm.				
9	Net Plot Area	:	484.08	Sqm.				
10	Bulldable Plot Area	:	484.08	Sqm.				
11	Permissible FSI	:	1.00					
12	Permissible BUA	:	484.08	Sqm.				
13	Proposed BUA	:	427.61	Sqm.				
14	Area for Assessment	:						
a)	On Plot/Land area	:						
	Residential	:	484.08 Sq.m.	x	100.00	=	Rs48,408.00	
	Commercial	:	0.00 Sq.m.	x	200.00	=	Rs0.00	
b)	On BUA	:						
	Residential	:	427.00 Sq.m.	x	250.00	=	Rs106,750.00	
	Commercial	:	0.00 Sq.m.	x	500.00	=	Rs0.00	
c)	On Construction Area Free of FSI	:	540.62 Sq.m.	x	200.00	=	Rs108,124.00	
	Total Development Charges						Rs263,282.00	



15	Development Charges Paid Vide							
a)	Receipt No.351552 dated 17/10/2015					=	Rs193,380.00	
b)	Receipt No.351553 dated 17/10/2015					=	Rs56,500.00	
c)	Receipt No.351556 dated 17/10/2015					=	Rs7,000.00	
d)	Receipt No.351557 dated 26/10/2015					=	Rs5,000.00	
e)	Receipt No.351558 dated 26/10/2015					=	Rs3,000.00	
							Rs274,880.00	
16	Balance development charges to be paid					=	Rs.	Nil
17	Date of Assessment							
18	Premium Components given free FSI :							
a)	Staircase	:	144.66	x	750	=	Rs108,495.00	
b)	Balcony	:	19.48	x	750	=	Rs14,610.00	
c)	Basement	:	148.58	x	750	=	Rs111,435.00	
d)	Pocket Terrace	:	105.50	x	450	=	Rs47,475.00	
e)	Proposed Lift Area	:	7.50	x	750	=	Rs5,625.00	
							Rs287,640.00	

COLOUR XEROX

मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०३
ई-मेल: vasaiVirarCorporation@yahoo.com

जावक क्र. : व.वि.श.म.
दिनांक :

VCMC/TP/CC/VP-5731/ 24-06 / 2015-16

Dated 9 /08/2015

- 19 Less : Premium Paid Vide
a) Receipt No. 404680 dated 17/10/2015 = Rs178,680.00
b) Receipt No. 404692 dated 20/10/2015 = Rs100,000.00
c) Receipt No. 404855 dated 05/11/2015 = Rs9,000.00
Rs287,680.00
- 20 Labour Cess Charges :
On Construction Area : [540.62 Sq.mt x 12000] 1% 64874.40
a) Paid vide Receipt No.404682 dated 17/10/2015 Rs67,835.00
Rs67,835.00
- 21 Balance Labour cess Charges to be paid = Nil
- 22 As requested by you vide letter _____ for balance payable amount, installment facility is hereby granted . The balance amount will attract 18% interest till the date of payment. The Schedule of payment is given below:

SCHEDULE OF PAYMENT

Sr. No.	Amount for Development Charges (in Rs.)	Amount for Premium Charges (in. Rs.)	Amount for fire Charges (in Rs.)	Due Date of Payment	Interest (in Rs.)
-----Nil-----					

COLOUR XEROX



Yours Faithfully,

[Signature]
Dy. Director of Town Planning
Vasai-Virar City Municipal Corporation

C.C. to
1 Ar. Umesh Kekre,
F-208, Vishwakarma,
Nagar, Bldg 3, Ambadi Rd.,
Vasai (W), Tal - Vasai,
Dist-nalghar

मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०६/०६
फॅक्स : ०२५० - २५२५२०९
ई-मेल : vasavirarcorporation@yahoo.com

जाबक क्र. : व.वि.श.स.
दिनांक :

VVCMC/TP/CC/NP-5731/2406/2015-16

9/10/2015

To,
Damji bhanushali,
Kishore kunj,
Behind Vartak Engineering college,
Navghar Vasai (W)
Tal :- Vasai, Dist :- Palghar.

Sub: **Commencement Certificate for proposed Residential Building on land bearing S.No.21 Plot No.43 of Village: Navghar, Taluka: Vasai, Dist: Palghar.**

Ref :

1. N.A Order No.NAP/SR/76 dated 13/03/1973.
2. TILR M.R. No. 978 dtd.12/10/1975 for measurement.
3. Your Licensed Engineer's letter dated 07/07/2015.

Sir/ Madam,

The Development Plan of Vasai Virar Sub Region is sanctioned by Government of Maharashtra vide Notification no TPS-1205/1548/CR-234/2005/UD-12 dated 09/02/2007. Keeping 113 EPS in pending. Further 5 EPS were approved vide Notification No. TPS-1208/1917/CR-89/09/UD-12 dtd. 13/03/2009, 31 EPS were approved vide Notification No.TPS-1208/1917/CR-89/09/UD-12 dtd 19/09/2009, Notification No. TPS-1208/1917/CR-89/08/UD-12 dtd 05/10/2009, 11 EPS were approved vide Notification No.TPS-1209/1917/CR-89/09 UD-12 dtd. 4th April 2012 and 1 EP was approved vide notification no.TPS-1214/975/CR-77/14/UD-12 dtd. 16th August 2014. Govt. entrusted Planning Authority functions for respective jurisdiction of Vasai-Virar City Municipal Corporation vide notification no. TPS-1209/2429/CR-262/2010/UD-12 dtd. 07/07/2010. Further Vasai Virar City Municipal Corporation is appointed by Govt.of Maharashtra as SPA for 21 villages. Arnala, Arnala Killa, Patilpada, Mukkam, Tembi, Kolhapur, Chandrapada, Tokri, Khairpada, Vasalai, Rangao, Doliv, Khardi, Khochiwada, Pall, Tivri, Octane, Tarkhad, Maljipada, Satpala & Kalamb, notification no. TPS-1214/UOR-54/CR-17/15/UD-12 dtd. The 21st February 2015. In the capacity of Municipal Corporation/Planning Authority for respective jurisdiction and SPA for 21 villages VVCMC is functioning as per MRTP Act 1966. The details of permission are as under:

The conditions mentioned in the letter No.VVCMC/TP/CC/VP-5731/..... dated .../10/2015 are binding on you. The details of the layout is given below:

1	Name of Assessee owner / P.A. Holder	:	Damji Bhanushali.
2	Location	:	Navghar
3	Predominant Land use	:	Residential
4	Gross Plot Area	:	484.08 Sq.mt.
5	Deductions	:	Nil
6	Net Plot Area	:	484.08 Sq.mt.
7	Buildable Plot Area	:	484.08 Sq.mt.
8	Permissible FSI	:	1.00
9	Permissible BUA	:	484.08 Sq.mt.
10	Proposed BUA	:	427.61 Sq.mt.



COLOUR XEROX

The details of the Buildings is given below:

Sr. No.	Predominant Building	Bldg No	No. of Floors	No. of flats	Built Up Area (in sq. mt.)
1.	Residential	1	Basement+ Stilt+4	17	427.61

मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल: vasalvirarcorporation@yahoo.com

जायक क्र. : व.वि.श.म.
दिनांक :

VVCMC/TP/CC/VP-5731/2406/2015-16

11
7/10/2015

- 1) The commencement certificate shall remain valid for a period of one year for the particular building under reference from the date of its issue (As per Section 48 of MR & TP Act, 1966 and Clause 2.42 & 2.6.9 of Sanctioned D.C. Regulations-2001).
- 2) The amount of Rs.21951/- (Rupees Ninety Eight thousand only) deposited vide receipt No.404681 dated 17/10/2015 with Vasai-Virar City Municipal Corporation as security deposit shall be forfeited either in whole or in part at the absolute discretion of the Corporation for breach of any building Control Regulation & Conditions attached to the permission covered by the Commencement Certificate. Such forfeiture shall be without prejudice to any other remedial right of the Corporation.
- 3) You shall transport all the construction material in a good transport system and the material shall not be stacked in unhygienic / polluting condition/on road without permission of VVCMC.
- 4) You shall see that water shall not be stored to lead to unhygienic conditions like mosquito breeding/disease prone conditions.
- 5) You shall provide drainage, sewerage, water storage systems strictly to the satisfaction of Vasai-Virar City Municipal Corporation. Else occupancy certificate shall not be granted to you, which may please be noted.
- 6) You have to fix a board of public notice regarding unauthorized covering of marginal open spaces before applying for occupancy certificate of next building as per the format finalized by Vasai-Virar City Municipal Corporation.
- 7) You shall develop the access road to the satisfaction of Vasai-Virar City Municipal Corporation as per the width as shown in the approved plan (D.P. Road/ access obtained as the case may be) before applying for Plinth Completion Certificate. You shall give detailed engineering report comprising reclamation level to be maintained, Storm Water drainage systems, sewerage systems and water supply (tank sizes etc) before applying for Plinth Completion Certificate.
- 8) You shall construct cupboard if any, as per D.C Regulations.
- 9) You shall provide Mosquito proof treatment in order to avoid Mosquito breeding to the satisfaction of VVCMC. Occupancy Certificate will not be granted if Mosquito treatment is not provided by providing Dr. Major Covells system of Mosquito proofing to control Malaria to the satisfaction of VVCMC.
- 10) You shall provide two distinct pipelines for potable and for non-potable water.
- 11) You shall provide Anti larvae treatment and avoid water logging in the construction sites to avoid Mosquito breeding to avoid dengue, Malaria and other vector borne diseases to the satisfaction of VVCMC. VVCMC will take actions as per various section of BMC if water logging and mosquito breeding has taken place. Otherwise work stop notices will be issued in public interest.
- 12) You shall provide the Rain Water Harvesting systems as per Govt. notification No.TBA-432001/2133/CR-230/01/UD-11 dtd. 10/03/2005 & TPB-4307/396/CR-24/2007/UD-11 dtd. 06/06/2007 by appointing the Rain Water Consultants empaneled by VVCMC. Occupancy Certificate shall be granted after certification of Rain Water Harvesting systems by said empaneled consultant of VVCMC.

COLOUR XEROX



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०३
ई-मेल: vasalvirarcorporation@yahoo.com

जाबक क्र. : व.वि.श.म.
दिनांक :

VVCMC/TP/CC/VP-5731/2406/2015-16

॥
१/१०/२०१५

- 13) You shall submit NOC from Chief Fire Officer before commencing the construction work above Plinth Completion Certificate., if applicable
- 14) You shall construct the compound wall before Plinth Completion Certificate.
- 15) You shall submit subsoil investigation report for structural stability & Rain water Harvesting purpose before Plinth completion Certificate.
- 16) You are responsible for the disputes that may arise due to Title/ Access matter. Vasai-Virar City Municipal Corporation is not responsible for any such disputes.
- 17) You shall not cut any tree which is existing on site. The existing tree shall be replanted by adopting suitable technology by taking permission from Vasai Virar city municipal Corporations. New trees shall be planted on the premises @ 30 per sq.m of BUA and 10@ per Sq.m in R.G. Further you shall submit NOC from tree Authority of VVCMC before applying for occupancy certificate regarding compliance to governing tree act also.
- 18) You shall provide flush tanks in all W.C/Tollets with dual valve system.
- 19) You shall do structural Audit for the buildings under reference after 30 years of completion as per Government of Maharashtra Act No.6 of 2009.
- 20) You shall plant the plants by taking the sapling/Plants available with Vasai Virar City Municipal Corporation. You shall contact DMC, Vasai-Virar City Municipal Corporation and shall plant the same as will be directed by DMC, VVCMC under intimation to this office.
- 21) You are responsible for obtaining various permissions from other authorities subsequent to grant of permission like revised N.A order, PWD NOC, NOC from Highway Authority, NOC from Railway, NOC from MSEB, MOEF, CRZ/wetlands etc., as may-be applicable and N.A TILR as required as per N.A order and other applicable compliances. If any of the compliances as per other Dept/Acts/ requirements are not done, only you shall face the consequence arising out of such lapse from your side and VVCMC is not responsible for the lapses from your side.
- 22) You are responsible for complying with all conditions of N.A. order/sale permission / other permissions of other authorities including MOEF/CRZ/wetlands etc. In case of any violation with reference to conditions of N.A. order / permissions of other Authorities, only you shall be responsible for the said violation and the same may call for actions by Concerned Authority as per their statutory provisions. Vasai Virar City Municipal Corporation has no role in the said matters. However if any conditions pertaining to validity of said orders are not complied like validity of N.A. order etc. Only you are liable for any actions as may be contemplated by the said authority notwithstanding the permission granted by VVCMC as the same need to be ensured by Concerned Authority.
- 23) As per notification no: TPB-4312/CR-45/2012/(I)/UD-11 dtd. 8th November 2013 from GOM U/s. 37 (1AA) (C) of MR & TP Act, 1966, you shall construct EWS/LIG housing in the form of tenements as prescribed in above notification at least to the extent of 20% of basic zone FSI. (Of areasq.m) which is earmarked in the drawing as enclosed and conditions (Specified in clause of the said notification) are strictly to be followed. For this purpose you shall contact Executive Engineer-1 Konkan Housing and Area Development Board, MHADA, Room No.169A, Mezzanine Floor, grihanirman Bhavan, Bandra (E), Mumbai-403 051 contact No. 02266405018.

COLORED XEROX



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल : vasaivirarcorporation@yahoo.com

जायक क्र. : व.वि.श.म.
दिनांक :

VVCMC/TP/CC/VP-5731/2406/2015-16

११/१०/२०१५

- 24) You shall take all precautionary measures as per various statutory provisions including provisions as contained in National Building code of India in order to avoid injury/loss to lives and property during construction and till the property is handed over to the subsequent legitimate owner of the property. If any such incident occurs you are responsible for the same and VVCMC is not responsible for your negligence, in providing various precautionary measures to avoid accidents leading to loss of life, injury or loss of property
- 25) Hon'ble High Court in PIL 87/2013 restricted the development on wetlands as identified by central Govt. wetlands atlas. You shall not carryout any permission on wetlands as identified in wetland atlas without permission from the Hon'ble High Court Mumbai.
- 26) You shall follow the MOEF notification and all other applicable notifications and guidelines issued by Central and State Governments for development of these lands by following all provisions including Hon'ble Court Orders.

Yours faithfully,

Dy. Director of Town Planning
Vasai-Virar City Municipal Corporation

COLOUR XEROX



Encl.: a/a.
c.c. to:

1. The Collector,
Office of the Collector, Palghar.
2. The Tahasildar
Office of the Tahasildar, Vasai .
3. Dy. Municipal Commissioner
Vasai-Virar City Municipal Corporation.
DMC-2
4. Asst. Commissioner, UCD,
Vasai-Virar city Municipal Corporation.
Ward office
5. Arch. Umesh Kekre
F,208.Bldg. no.3,Vishwakarma Nagar,
Ambadi road,Vasai(W)401202.

मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल: vasaivirarcorporation@yahoo.com

जायक क्र. : च.वि.श.म.
दिनांक :

VVCMC/TP/CC/VP-5731/2406/2015-16

9/11/2015

CONDITIONS FOR COMMENCEMENT CERTIFICATE

The set of the conditions as mentioned below shall be read with the Commencement Certificate of the particular building as mentioned.

1. The commencement certificate is liable to be revoked by the Municipal Corporation if :-
 - a) The development work in respect of which permission is granted under this certificate is not carried out or the use thereof is not in accordance with the sanctioned plans.
 - b) Any of the conditions subject to which the same is granted or any of the restrictions imposed by the Municipal Corporation is contravened.
 - c) The Commissioner, VVCMC is satisfied that the same is obtained by the applicant through fraud or misrepresentation and the applicant and every person deriving title through or under him, in such event shall be deemed to have carried out the development work in contravention of Section 43 or 45 of the Maharashtra Regional and Town Planning Act, 1966.
2. The applicant shall :-
 - a) Give notice to the Municipal Corporation immediately after starting the development work in the land under reference.
 - b) Give notice to the Municipal Corporation on completion upto the plinth level & obtain plinth completion certificate before the commencement of the further work.
 - c) Give written notice to the Municipal Corporation regarding completion of the work.
 - d) Obtain an occupancy certificate from the Municipal Corporation.
 - e) Permit authorized officers of the Municipal Corporation to enter the building or premises for the purpose of inspection with regard to observing building control regulations and conditions of the certificate.
 - f) Pay to MUNICIPAL CORPORATION the development charges as indicated in Appendix "A" along with interest @ 18% p.a. on the balance amount. If the rate of interest is enhanced by MUNICIPAL CORPORATION the same will be applicable. The applicant shall pay to MUNICIPAL CORPORATION the development charges as agreed in the undertaking submitted by him on
 - g) Install a 'Display Board' on the most conspicuous place on site indicating :-
 - i. Name & address of owner /developers, architect, Structural Engineer and contractor.
 - ii. S.NO./CTS No., Ward No., Village Name alongwith description of its boundaries.
 - iii. Order number and date of grant of development permission/redevelopment permission issued by Municipal Corporation.
 - iv. FSI permitted.
 - v. No. of residential/commercial flats and shops with their areas.
 - vi. Address where copies of detailed approved plans shall be available for inspection.

COLOUR XEROX



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरधनी : ०२५० - २५२५१०१ / ०२६३६०४/०५/०६
फॅक्स : ०२५० - २५२५१०३
ई-मेल: vasaiVirarcorporation@jysheco.com

जाचक क्र. : व.वि.श.म.
दिनांक :

- vii. A notice in the form of an advertisement, giving all the details mentioned in i) to vi) above shall also be published in 2 widely circulated news papers one of which should be in regional language.
3. The structural Design including the aspects pertaining to seismic activity, Building materials, Plumbing Services, Fire Protection, Electrical Installation etc. shall be in accordance with the provisions (except for the provisions in respect to Floor Area Ratio) prescribed in the National Building Code amended from time to time by the Bureau of India Standards.
4. The commencement certificate shall remain valid for a period of one year for the particular building under reference from the date of its issue.
5. The conditions of the certificate shall be binding not only on the applicant but also on his successors, and every person deriving title through or under them.
6. A certified copy of the approved plan shall be exhibited on site.
7. The land vacated in consequence of the enforcement of the set-back rule shall form part of the public street.
8. No new building or part thereof shall be occupied or allowed to be occupied or used or permitted to be used by any person until occupancy certificate has been granted by this Municipal Corporation. If the occupancy is reported before grant of occupancy certificate the security deposit of the said building forfeited and unauthorized Occupancy Charges and other charges as applicable.
9. This permission does not entitle you to develop the land which does not vest in you.
10. You shall provide over-head water tank on the building as per the Bombay Municipal Corporation standards and to the satisfaction of Vasai-Virar City Municipal Corporation.
11. You should approach Executive Engineer (MSEB) for the temporary power requirement, location of the transformer etc. The permanent power connection from MSEB can be obtained only after getting the necessary occupancy certificate from this Municipal Corporation.
12. The transfer of the property under reference can be effected only after the necessary approval from Municipal Corporation or occupancy certificate is obtained by the applicant before any such transfer.
13. You shall provide at your own cost, the Infrastructural facilities within the plot as stipulated by the Municipal Corporation (Internal Access, channelisation of water, arrangements of drinking water, arrangements for conveyance, disposal of sullage and sewage, arrangement of collection of solid waste) before applying for occupancy certificate. Occupancy Certificate shall not be granted unless all these arrangements are found to the satisfaction of Municipal Corporation.
14. As far as possible no existing tree shall be cut. If this is unavoidable, twice the number of trees cut shall be planted on site.

COLOR XEROX



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल : vasalvirarcorporation@yahoo.com

जावक क्र. : व.वि.श.म.
दिनांक :

15. The grant of this permission is subject to the provisions of any other law for the time being in force and that may be applicable to the case e.g. Urban Land (Ceiling & Regulations) Act 1969 & getting the building plans approved from various authorities.
16. You shall provide potable water to the consumer / occupier of tenements/units before applying for occupancy certificate. The possession of said property shall not be given before occupancy certificate be granted only after verifying the provision of potable water to the occupier.
17. The owner shall get the approved layout demarcated on the site by the Surveyors of the TILR, Thane, and shall submit to the Municipal Corporation the measurement plan certified by the TILR, Vasai for record. The demarcation of approved layout on the site shall be carried out so as not to alter /reduce the dimensions and area of the roads, open space or other reservations. The demarcated layout measurement plan certified by TILR shall be submitted before grant of occupancy certificate. The conditions prescribed in N.A order as regards TILR preparation is binding on you.
18. The owner shall provide at his own cost the following infrastructural facilities of such standards (i.e. standards relating to design, material or specifications) as stipulated by the Municipal Corporation.
 - a) Internal access roads along with storm water drains.
 - b) Channelization of water courses and culverts, if any.
 - c) The arrangements of water supply and drainage disposal shall be made by the individual owner of the plot at his own cost.
 - d) Arrangements for collection of solid waste.
 - e) All fire fighting requirement along with necessary accessories as prescribed in DCR and national building code and as per chief fire officer remarks.
 - f) Rain Water Harvesting systems and solar assisted Water Heating systems.
19. The low-lying areas shall be filled as per formation levels indicated on the development plan prepared for Virar-Vasai Sub-Region. Further, the required arrangements of storm water drain and septic tank /STP or any other arrangement as may be prescribed, shall have to be done according to the specifications.
20. The owner shall permit the use of the internal access roads to provide access to an adjoining land.
21. The owner shall submit to the Municipal Corporation the scheme of the development of 15% or 20% depending on plot area compulsory recreational space and develop it in accordance with the approved scheme.
22. The owner shall not further sub-divide or amalgamate plots without obtaining prior approval of the Municipal Corporation.

COLOUR XEROX



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल: vasaivirarcorporation@yahoo.com

जावक क्र. : व.वि.श.म.
दिनांक :

COLOUR XEROX

23. The owner shall not dispose off any plot or tenement unless the infrastructural facilities mentioned in conditions No. 20 above are actually provided.
24. If the owner does not make adequate arrangements for conveyance and disposal of sullage and sewage before disposal of the plots, he shall, through appropriate agreements, ensure that this obligation is cast upon the buyers of the plot or tenements.
25. The owner shall observe all the rules in force regarding over head/underground electric lines / transmission lines/utilities passing through the layout while designing the individual buildings and while getting the approval of the concerned authority.
26. No construction on sub-divided plots shall be allowed unless internal road and storm Water Drains/Sewerage are constructed to the satisfaction of the appropriate authority.
27. Open space shown in the layout shall be kept open permanently and shall be handed over to the appropriate authority.
28. No plot should be disposed off unless the sale permission under Section 43 of the B.T. & A.L. Act is obtained from the sub-divisional officer concerned if the land under reference is a restricted tenure land.
29. No development shall be taken up unless the N.A. Permission is obtained from the Collector under the provisions of M.L.R. Code 1966, and also all necessary permission as applicable depending on the class of the land type of tenure type of Occupant etc. is obtained by the concerned owner applicant after completing all the legal formalities VVCMC is not responsible for any lapse on your part in obtaining various permissions required as per other acts of both state and central Govt., etc.
30. If the plot is intended to be sold or otherwise disposed off by the owner, it shall be done by the owner subject to the conditions mentioned in this order. He shall invariably make specific mention about these conditions in the deed to be executed by him.
31. This order is liable for cancellation on contravention or breach of any of the conditions of this order.
32. Notwithstanding anything contained in the Commencement Certificate conditions, it shall be lawful for the Municipal Corporation to direct the removal or alteration of any structures erected or the use contrary to the provisions of this grant. Municipal Corporation may cause the same to be carried out and recover the cost of carrying out the same from the grantee / successors and every person deriving title through or under them.



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दुरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल: vasalvirarcorporation@yahoo.com

जावक क्र. : व.वि.श.म.
दिनांक :

COLOUR XEROX

33. The owner shall have to provide water in requisite quantity from the sources to the prospective flat buyers for perpetuity.
34. The plinth level will be 600 mm above the nearby road level (top of camber).
35. Separate stacks for ground floor and upper floors for sewerage disposal shall be provided.
36. Drinking water wells should be well built and well protected.
37. If the length of the proposed building exceeds 45 M, the expansion joints shall be provided at suitable places with suitable materials.
38. While extracting water from underground, you will strictly follow the instructions given by Sr. Geologist of the G.S.D.A. to ensure that proper quality and quantity of water is available to you and no contamination of the water source and its surroundings takes place.
39. You will not take up any development activity on the aforesaid property till the court matter is pending, if any or in any court of law relating to this property and the responsibility of following the court order strictly lies with you consequences due to violation of court order shall be borne by you. VVCMC is not responsible for any violations.
40. You will make suitable arrangements for temporary accommodation and permanent accommodation of the tenants, if any while redeveloping the scheme and will also give a proposal to accommodate them. Plinth Completion Certificate shall be issued only after such a proposal is received.
41. You will construct the society room as proposed and approved in the plan and it will not be used other than for society's purpose. This society room shall be handed over to the Co-operative housing Society to be formed in due course of time.
42. For the portion of the compound wall rounded off at the corner at road junctions, M.S. grills over 0.75 m of brick work, upto the height of 1.5 m from the ground shall be provided.
43. This development permission shall enable you to construct upto plinth level only. For further construction, plinth completion certificate has to be obtained from this office.
44. You shall not cut any tree which is existing on site. The existing tree shall be replanted by adopting suitable technology by taking permission from Vasai Virar city municipal Corporations. New trees shall be planted on the premises @ 30 per sq.m of BUA and 10@ per Sq.m in R.G. Further you shall submit NOC from tree Authority of VVCMC before applying for occupancy certificate regarding compliance to governing tree act also.



मुख्य कार्यालय, विरार
विरार (पूर्व),
ता. वसई, जि. पालघर - ४०१ ३०५.



दूरध्वनी : ०२५० - २५२५१०१ / ०२/०३/०४/०५/०६
फॅक्स : ०२५० - २५२५१०७
ई-मेल: vasaivirarcorporation@yahoo.com

जावक क्र. : व.वि.श.म.
दिनांक :


WCMC/TP/CC/VP-5731/2406 / 2015-16

९ / 11 / 2015

45. Only one unit shall come up in each gala and no sub-division of gala for subletting or accommodating other unit shall be allowed.
46. You shall submit detailed proposal for rain water harvesting and solid waste disposal to treat dry and organic waste separately before applying for plinth completion certificate.
47. You shall submit detailed proposal for sewage treatment plant by way of package treatment plant, recycling of water and solid waste disposal through composting vermiculture project before applying for plinth completion certificate. You shall use fly ash bricks or blocks or clay fly ash bricks or cement fly ash bricks or blocks or similar products of a combination of aggregate of them in the construction of the project and as per the notification of Ministry of Environment & Forest Govt. of India date 27th Aug. 2003.
48. Notwithstanding anything contained in the Development Control Regulations, the Development Plan provisions or the approvals granted / being granted to you; it shall be lawful on the part of the Municipal Corporation to impose new conditions for compliance as may be required and deemed fit to adhere to any general or specific orders or directives of any Court of Law, Central / State Government, Central / State PSU, Local Authority or any public authority as may be issued by them from time to time.
49. You have to fix a board of public notice regarding unauthorised covering of marginal open spaces before applying for occupancy certificate of next building as per the format finalized by MUNICIPAL CORPORATION.
50. You shall develop 6.0m wide access road of W.B.M. standard before Commencement of work.



COLOUR XEROX


Dy. Director of Town Planning
Vasai-Virar City Municipal Corporation