in replying please quote No. and date of this letter.

Intimation of Disapproval under Section 346 of the Mumbai Municipal Corporation Act, as amended up to date.

Dy. Ch. Eng. (B.P.) Special Cell, Gr Fif: Municipal Training Centre, Raheja Vihar Complex, Behind Indian Shipping Corpn., Powal, Chandivall Farm Road, Andherl (East), Mum-400072

No. E.B./CE/

BS/A of 20 CHE / 107 / BP (Spl. Cell) / AMW / 337

MEMORANDUM

Municipal Office.

M/s. Joynest Premises Pvt. Ltd. Concessionaire to EE (BCD) PWD, GoM, 20 CTS No. 469-A, Chembur, Mumbai – 400071.

With reference to your Notice, letter No. 4400 dated 20 and delivered on 07.10.2011 20 and the plans, Sections Specifications and Description and further particulars and details of your buildings at Proposed Building on sub plot 'E' in Layout on plot bearing CTS No 469A of village Chembur, Mumbai.

A. CONDITIONS TO BE COMPLIED WITH BEFORE STARTING THE WORK BEFORE PLINTH C.C.

- That the commencement certificate under Sec.45/69(1)(a) of the M.R.& T.P. Act will not be obtained before starting the proposed work.
- That NOC from Tree Authority will not be submitted and adequate care will not be taken to safeguard the trees existing on the plot while carrying out construction work.
- That a Janata Insurance Policy or policy to cover the compensation claims arising out
 of Workmen's Compensation Act 1923 will not be taken out before starting the work
 and will not be renewed during the construction of work.
- That the No Objection Certificate from Hydraulic Engineer for the proposed development will not be obtained and his requirements will not be complied with.
- That the remarks from Asst. Engineer, Water Works regarding location, size capacity
 of the suction tank, overhead storage tank for proposed and existing work will not be
 submitted before starting the work and his requirements will not be complied with.
- That the debris management plan shall not be submitted to S.W.M. Department.
- That the NOC Chief Engineer (M& E) shall not be submitted for purpose of artificial light & ventilation.
- That No dues pending certificate from Asst. Engineer (W.W) "M" Ward before CC.

() That was				
, and property of the property	If guillers and down hippy are not the	4 14 1 · · ·		• .
of the root on the mit it	er gutters and down pipes are not interstreet.	nded to be put to prevent wat	erdron-: c	· ` · · · · · · · · · · · · · · · · · ·
or the root on the bublic.	street.	I Francis Wall	er grohbrug Mün	ئەمىدە the leavai
	· ·	·-		- m. c. v. c. m(AC)
			1.	

() That the drainage work generally is not intended to be executed in accordance with the Municipal

Your attention is drawn to the Special Instructions and Note accompanying this Intimation of Disappro val.

Executive Engineer, Building Proposals,

Zone, Sp. Ch. Wards.

SPECIAL INSTRUCTIONS

- (1) THIS INTIMATION GIVES NO RIGHT TO BUILD UPON GROUND WHICH IS NOT YOUR PROPERTY.
- (2) Under Section 68 of the Bombay Municipal Corporation Act, as amended, the Municipal Commissioner for Greater Mumbai has empowred the City Engineer to exercise, perform and discharge the powers, duties and functions conferred and imposed upon and vested in the Commissioner by Section 346 of the said Act.
 - (3) Under Byelaw, No. 8 of the Commissioner has fixed the following levels:-

"Every person who shall erect as new domestic building shall cause the same to be built so that every part of the plinth shall be—

- "(a) Not less than, 2 feet (60 cms.) above the centre of the adjoining street at the nearest point at which the drain from such building can be connected with the sewer than existing or thereafter to be-laid in such street"
- "(b) Not less than 2 feet (60 cms.) above every portion of the ground within 5 feet (160 cms.) of such building.
 - "(c) Not less than 92 ft. () meters above Town Hall Datum."
- (4) Your attention is invited to the provision of Section 152 of the Act whereby the person liable to pay property taxes is required to give notice of erection of a new building or occupation of building which has been vacant, to the Commissioner, within fifteen days of the completion or of the occupation whichever first occurs. Thus compliance with this provision is punishable under Section 471 of the Act irresepective of the fact that the valuation of the premises will be liable to be revised under Section 167 of the Act, from the earliest possible date in the current year in which the completion on occupation is detected by the Assessor and Collector's Department.
- (5) Your attention if further drawn to the provision of Section 353-A about the necessary of submitting occupation certificate with a view to enable the Municipal Commissioner for Greater Mumbai to inspect your permises and to grant a permission before occupation and to leavy penalty for non-compliance under Section 471 if necessary.
- (6) Proposed date of commencement of work should be communicated as per requirements of Section 347(1)(aa) of the Bombay Municipal Corporation Act.
 - (7) One more copy of the block plan should be submitted for the Collector, Mumbai Suburbs District.
- (8) Necessary permission for Non-agricultural use of the land shall be obtained from the Collector Mumbai Suburban District before the work is started. The Non-agricultural assessment shall be paid at the site that may be fixed by the Collector, under the Land Revenue Code and Rules thereunder.

Attention is drawn to the notes Accompanying this Intimation of Disapproval.

CHE / 107 / BP (SPL. CELL) / AMW / 337

- That the regular sanction / proposed lines and reservation will not be got demarcated at site through A.E. (Survey) / E.E.(T.C.) / E.E.(D.P.) / DILR before applying for C.C.
- That the specification for layout /DP/ or access roads / development of setback land will not be obtained from Executive Engineer (Road Construction) before starting the construction work and the access and setback land will not be developed accordingly including providing street lights and S.W.D., the completion certificate will not be obtained from Executive Engineer (R.C)/Executive Engineer (S.W.D) E.S. before submitting building completion certificate.
- That the remarks regarding surface drainage arrangement will not be obtained from Executive Engineer (S.W.D.) and arrangement as per his remarks shall not be made at site.
- That the requirements / N.O.C. of concerned Electric Supply Co. will not be obtained and the requirement thereof will not be proposed in the development.
- That the clearance certificate from Assessment Department regarding upto date payment of Municipal taxes etc. will not be submitted.
- 14. That the requirement of bye law 4(C) will not be complied with before starting the drainage work and in case Municipal sewer is not laid, the drainage work will not be carried on as per the requirement of Executive Engineer (Sewerage Project), Planning & completion certificate from him will not be submitted.
- That the N.O.C. from Insecticide Officer shall not be submitted.
- 16. That the C.C. shall not be asked unless payment of advance for providing treatment at construction site to prevent epidemics like Dengue, Malaria etc. is made to the Insecticide Officer of the concerned ward office and provision shall not be made as and when required by Insecticide Officer for inspection of water tanks by providing safe and stable ladder, etc. and requirements as communicated by the Insecticide Officer shall not be complied with.
- 17. That remarks from SP(P&D) for drainage connection shall not be submitted.
- That the NOC from M.G.L. is not obtained.
- That the authorized private pest control agency to give anti-larval treatment on construction site shall not be appointed and conditions of circular u/No.AMC/WS/H/9346/ 29.3.2010 shall not be complied with.
- That the Licensed Structural Engineer will not be appointed, supervision memo as per appendix XI Regulation 5(3)(IX) will not be submitted by him.
- 21. That the structural design and calculations for the proposed work considering seismic forces as per I.S. Code Nos.456-2000, 13920 1993, 4326 and 1893 2002 as per circular u.no.CE/PD/11945/1 dated 2.2.2006 for existing building showing adequacy thereof to take up additional load will not be submitted by him.

Dy. Ch. Eng. (B.P.) Special Cell, Raheja Vihar Complex, Behind Indian Shipping Corpn., Powal, Chandivali Farm Road, Andheri (East), Mum-400072

CHE / 107 / BP (SPL. CELL) / AMW / 337

- 22. That the qualified registered site supervisor through architect/structural engineer will not be appointed before applying for C.C.& his name and license No. duly revalidated will not be submitted.
- 23. That the soil investigation report from Geologist shall not be submitted.
- 24. That adequate care in planning, designing and carrying out construction will not be taken in the proposed building to provide for the consequence of settlement of floors and plinth filling etc.
- That the Architect shall not submit the quarterly progress report of the proposed work.
- 26. That the work of construction shall not be carried out between 7.00 a.m. to 7.00 p.m.
- 27. That the compound wall is not constructed on all sides of the plot clear of road widening line with foundation below the bottom of road side drain without obstructing the flow of rain water from the adjoining holding to prove possession of holding before starting the work as per D.C. Regulation No.38(27).
- 28. That the low lying plot will not be filled up to reduced level of atleast 92 T.H.D.or 6" above adjoining road level whichever is higher with murum, earth, boulders, etc. and will not be leveled, rolled, consolidated and sloped towards road side before starting the work.
- That the existing structure proposed to be demolished will not be demolished or necessary phase programme with agreement will not be submitted and got approved before C.C.
- That the adequate & decent temporary sanitary accommodation will not be provided for construction workers on before starting the work.
- That the carriage entrance shall not be provided before starting the work.
- That the board mentioning the name of Architect/Owner shall not be displayed on site.
- 33. That the Indemnity Bond indemnifying the Corporation for damages, risks, accidents, etc. and to the occupiers and an undertaking regarding no nuisance will not be submitted before C.C./starting the work.
- 34. That the registered undertaking and additional copy of plan shall not be submitted for agreeing to hand over the setback land free of compensation and that that the setback handing over certificate will not be obtained from Ward Officer and the ownership of the setback land will not be transferred in the name of M.C.G.M.
- That the registered undertaking in prescribed proforma agreeing to demolish the excess area if constructed beyond permissible F.S.I. shall not be submitted before asking for C.C.

CHE / 107 / BP (SPL. CELL) / AMW / 337

- That the registered undertaking to form Co-op Housing society will not be submitted before starting the work.
- That the undertaking for paying additional premium due to increase in land rate as and when demanded shall not be submitted.
- 38. That the registered undertaking from the owner stating that they will not object development of the neighbouring plot which may involve deficiency in open space shall not be submitted
- 39. That the registered undertaking from the owner to incorporate a clause in sale agreement with prospective buyer that the said building is constructed with deficiency in open space shall not be submitted.
- 40. That the area reserved for parking shall not be used / utilized for the purpose of parking only and registered undertaking to that effect shall not be submitted.
- 41. That the registered undertaking indemnifying the M.C.G.M. against any litigation arising out of hardship to user in case of the failure of mechanized system / nuisance due to mechanical system to the building under reference and to the adjoining wing / adjoining building shall not be submitted.
- 42. The basement will not be comply with the basement rules & regulation regarding height ventilation user etc. and register under taking for not misuse the basement shall not be submitted.
- That the extra water and sewerage charges will not be paid to Assistant Engineer, Water Works 'M' Ward before C.C.
- 44. That the development charges as per M.R.T.P. (amendment) Act 1992 will not be paid.
- That the proposal will contravene the section 251(A)(A) of the Mumbai Municipal Corporation Act.
- That the requirements as per Circular No. CE/PD/12387 of 17/03/2005 shall not be complied with during the execution of work.
- That the NOC of Ex. Eng. (BCD) PWD for utilization of fungible FSI shall not be submitted before C.C.
- 48. That approval of Chief Architect, Govt. of Maharashtra (PWD) shall not be submitted for plans for development on subplot 'E' as per tender clause of 4.8 of scope of work Volume II of tender document.
- That the time extension for completion of project EE (BCD) PWD shall not be obtained and submitted to this Office.
- 50. That the NOC from EE (BCD) PWD to start the work on subplot E as per clause 3.1b of agreement shall not be submitted.

Dy Ch Eng (B.P.) Special Cell.
Cr + IP, Municipal Training Centro,
Behind Indian Shipping Corpn.
Fowal, Chandivall Farm Road.
Ancharl (East), Mum-400072

CHE / 107 / BP (SPL. CELL) / AMW / 337

B. CONDITIONS TO BE COMPLIED WITH BEFORE FURTHER C.C.

- That the notice under Sec. 347(1)(a) of the Mumbai Municipal Corporation Act will not be sent for intimating the date of commencement of the work.
- That this office will not be intimated in prescribed proforma for checking the opens spaces and building dimensions as soon as the work upto plinth is completed.
- That the plinth stability certificate from Registered Structural Engineer shall not be submitted.
- That the N.O.C. from Civil Aviation Department will not be obtained for the proposed height of the building.
- That the setback area shall not be cleared off and merged into the road.
- That the setback area shall not be handed over to MCGM.

C. GENERAL CONDITIONS TO BE COMPLIED WITH BEFORE O.C.

- That the certificate to the effect that the licensed surveyor has effectively supervised the work and has carried out tests for checking leakages through sanitary blocks, termites, fixtures, joints in drainage pipes etc. and that the workmanship is found very satisfactory shall not be submitted.
- That one set of plans mounted on canvas will not be submitted.
- That the structural stability certificate from registered structural engineer on the project shall not be submitted.
- That the final RCC drawings certified by registered structural engineer shall not be submitted.
- That the completion certificate from the licensed Site supervisor on the project shall not be submitted.
- The work completion certificate by Architect / licensed surveyor on the project shall not be submitted.
- That separate PR Card for subplot E shall not be submitted.
- That separate PR Card in the name of MCGM for setback area shall not be submitted
- That the certificate from Lift Inspector regarding satisfactory installation and operation of lift will not be submitted.
- That Final NOC from CFO shall not be submitted.
- 11. That the final NOC from S.G. shall not be submitted.
- That final NOC from Ch.E (M&E) for artificial light ventilation shall not be submitted.

CHE / 107 / BP (SPL. CELL) / AMW / 337

- That DCC from licensed plumber shall not submitted with acceptance of AE (BP).
- That the completion certificate from Ex. Engr. (S.P.) for drainage lines and connections shall not be submitted.
- That the completion certificate from Executive Engineer (S.W.D.) will not be obtained and submitted before applying for occupation certificate.
- That the completion from electric supply company regarding the installation of substation shall not be submitted.
- 17. That the requisitions of clause No.45 & 46 of D.C.R.91 shall not be complied with.
- 18. That the debris will not be removed before submitting the building completion certificate and requisite deposit will not be paid before starting the work towards faithful compliance thereof.
- That the provision for rain water harvesting as per design prepared by consultant in the field shall not be made to the satisfaction of Municipal Commissioner.
- That some of the drains will not be laid internally with C.I. pipes.
- That the dust bin will not be provided as per C.E.'s circular No. CE/9296/11 of 26.6.1978.
- 22. That 10 ft. wide paved pathway upto staircase will not be provided.
- 23. That the surrounding open spaces, parking spaces and terrace will not be kept open and un-built upon and will not be levelled and developed before requesting to grant permission to occupy the building or submitting the B.C.C. whichever is earlier.
- 24. That the name plate/board showing plot No.name of the building etc. will not be displayed at a prominent place before O.C.C./B.C.C.
- That the parking spaces shall not be provided as per D.C. Regulation No.36.
- 26. That the provision will not be made for making available water for flushing and other non-potable purposes through a system of borewell and pumping that water through a separate overhead tank which will be connected to the drainage system and will not have any chances of mixing with the normal water supply of the Corporation.
- That the adequate provision for post-mail boxes shall not be made at suitable location on ground floor /stilt.
- 28. That the every part of the building construction and more particularly, overhead tank will not be provided with a proper access for the staff of Insecticide Officer with a provision of temporary but safe and stable ladder etc.

Dy. Ch. Eng. (B.P.) Special Cell
St. Fif. Municipal Training Centre
Behind Indian Shipping Corpr.
Powal. Chandivall Farm Road.
Ancherl (East), Mun-400072

CHE / 107 / BP (SPL. CELL) / AMW / 337

- 29. That the infrastructural works such as; construction of handholds/manholes, ducts for underground cables, concealed wiring inside the flats/rooms, rooms/space for telecom installations etc. required for providing telecom services shall not be provided
- 30. That the Vermiculture bins for disposal of wet waste as per the design and specification of Organisations / individuals specialized in this field, as per the list furnished by Solid Waste Management Department of MCGM, shall not be provided to the satisfaction of Municipal Commissioner.
- That B.C.C. will not be obtained and I.O.D. and debris deposit etc. will not be claimed for refund within a period of 6 years from the date of its payment.
- D. CONDITIONS TO BE COMPLIED WITH BEFORE B.C.C.
- That certificate under Section 270-A of the Bombay Municipal Corporation Act will not be obtained from H.E.'s department regarding adequacy of water supply.

Executive Engineer (Building Proposal-Spl. Cell)

CC: 1) Ex. Engineer (BCD) PWD

2) Chief Architect, PWD (GoM)

3) M/s. Aakar Architects & Consultants

4) Asst. Commissioner 'M/W' Ward

5) A.E. (W.W) 'M/W' Ward

6) A.A&C 'M/W' Ward

7) Collector M.S.D.

Executive Engineer
(Building Proposal -Spl. Cell)

NOTES

- (1) The work should not be started unless objection are complied with
- (2) A certified set of latest approved plans shall be displyed on site at the time of commencement the work and during the progress of the construction work.
- (3) Temporary permission on payment of deposite should be obtained any shed to house and store for constructional purposes, Residence of workmen shall not be allowed on site. The temporary structures for storing constructional material shall be demolished before submission of building completion certificate and a certificate signed by Architect submitted along with the building completion certificate.
- (4) Temporary sanitary accommodation on full flusing system with necessary drainage arrangement should be provided on site workers, before starting the work.
- (5) Water connection for constructional purpose will not be given until the hoarding is constructed and application made to the Ward Officer with the required deposite for the construction of carriage entrance, over the road side drain.
 - (6) The owners shall intimate the Hydraulic Engineer or his representative in Wards atleast 15 days prior to the date of which the proposed construction work is taken in hand that the water existing in the compound will be utilised for their construction works and they will not use any Municipal Water for construction purposes. Failing this, it will be presume that Municipal tap water has been consumed on the construction works and bills preferred against them accordingly.
 - (7) The hoarding or screen wall for supporting the depots of building materials shall be constructed before starting any work even though no materials may be expected to be stabled in front of the property. The scaffoldings, bricks metal, sand preps debrics, etc. should not be deposited over footpaths or public street by the owner/architect/their contractors, etc. without obtaining prior permission from the Ward Officer of the area.
 - (8) The work should not be started unless the manner in obviating all the objection is approved by this department.
 - (9) No work should be started unless the structural design is approved.
- (10) The work above plinth should not be started before the same is shown to this office Sub-Engineer concerned and acknowledgement obtained from him regarding correctness of the open spaces & dimension.
- (11) The application for sewer street connections, if necessary, should be made simultaneously with commencement of the work as the Municipal Corporation will require time to consider alternative site to avoid the excavation of the road an footpath.
- (12) All the terms and conditions of the approved layout/sub-division under No. of should be adhered to and complied with.
- (13) No Building/Drainage Completion Certificate will be accepted non-water connection granted (except for the construction purposes) unless road is constructed to the satisfaction of the Municipal Commissioner as per the provision of Section 345 of the Bombay Municipal Corporation Act and as per the terms and conditions for sanction to the layout.
- (14) Recreation ground or amenity open space should be developed before submission of Building Completion Certificate.
- (15) The acces road to the full width shall be constructed in water bound macadam before commencing work and should be complete to the satisfaction of Municipal Commissioner including asphalting lighting and drainage before submitton of the Building Completion Certificate.
- (16) Flow of water through adjoining holding or culvert, if any should be maintained unobstructed.
- (17) The surrounding open spaces around the building should be consolidated in Concrete having broke glass pieces at the rate of 125 cubic meters per 10 sq. meters below payment.
- 18) The compound wall or fencing should be constructed clear of the road widening line with foundation below level of bottom of road side drain without obstructing flow of rain water from abjoining holding before starting the work to prove the owner's holding.
- 19) No work should be started unless the existing structures proposed to be demolished are demolished.

- (20) This Intimation of Disapproval is given exclusively for the purpose of enabling you to proceed further with the arrangements of obtaining No Objection Certificate from the Housing commissioner under Section 13 (h) (H) of the Rent Act and in the event of your proceeding with the work either without an inimation about commencing the work under Section 347 (1) (aa) or your starting the work without removing the structures proposed to be removed the act shall be taken as a severe breach of the conditions under which this Intimation of Disapproval is issued and the sanctioned will be revoked and the commencement certificate granted under Section 45 of the Maharashtra Regional and Town Planning Act, 1966, (12 of the Town Planning Act), will be with drawn.
- (21) If it is proposed to demolish the existing structures by negotiations with the tenants, under the circumstances, the work as per approved plans should not be taken up in hand unless the City Engineer is satisfied with the following:-
 - Specific plans in respect of eviciting or rehousing the existing tenants on hour stating their number and the
 area in occupation of each.
 - (ii) Specifically signed agreement between you and the existing tenants that they are willing to avail or the alternative accommodation in the proposed structure at standard rent.
 - (iii) Plans showing the phased programme of construction has to be duly approved by this office before starting the work so as not to contravene at any stage of construction, the Development control Rules regarding open spaces, light and ventilation of existing structure.
- (22) In case of extension to existing building, blocking of existing windows of rooms deriving light and its from other sides should be done first before starting the work.
- (23) In case of additional floor no work should be start or during monsoon which will same arise water leakage and consequent nuisance to the tenants staying on the floor below.
- (24) the bottom of the over hand storage work above the finished level of the terrace shall not be more than 1 metre.
- (25) The work should not be started above first floor level unless the No Objection Certificate from the Civil Aviation Authorities, where necessary is obtained.
- (26) It is to be understood that the foundations must be excavated down to hard soil.
- (27) The positions of the nahanis and other appurtenances in the building should be so arranged as not to necessitate the laying of drains inside the building.
- (28) The water arrangement must be carried out in strict accordance with the Municipal requirements.
- (29) No new well, tank, pond, cistern or fountain shall be dug or constructed without the previous permission in writing of the Municipal Commissioner for Greater Mumbai, as required in Section 381-A of the Municipal Corporation Act.
- (30) All gully traps and open channel drains shall be provided with right fiting mosquito proof covers made of wrought iron plates or hinges. The manholes of all jisterns shall be covered with a properly fitting mosquito proof hinged cast iron cap over in one piece, with locking arrangement provided with a bolt and huge screwed on hightly serving the purpose of a lock and the warning pripes of the ribbet pretessed with screw or dome shape pieces (like a garden mari rose) with copper pipes with perfictions each not exceeding 1.5 mm. in diameter, the cistern shall be made easily, safely and permanently a ceasible by providing a firmly fixed iron ladder, the upper ends of the ladder should be earmarked and extended 40 cms. above the top where they are to be fixed an its lower ends in cement concrete blocks.
- (31) No broken bottles should be fixed over boundary walls. This prohibition refers only to broken bottles to not to the use of plane glass for coping over compound wall.
- (32) (a) Louvres should be provided as required by Bye-law No. 5 (b).
 - (b) Lintels or Arches should be provided over Door and Window opening.
 - (c) The drains should be laid as require under Section 234-1 (a).
 - (d) The inspection chamber should be plastered inside and outside.
- (33) If the proposed aditional is intended to be carried out on old foundations and structures, you will do so at your own risk.

Executive Engineer, Building Proposals
ZonesWards